Roofiqo

ESTIMATE

Roofing LLC

8 Roofing St, Brooklyn, NY 11201,
+1 234 456 7891 | hello@roofiqo.com
TAX ID: 12-3456789

PROJECT NAME
Smith Residence

ISSUE DATE
2/25/2026

PREPARED FOR

Smith Peter

Newbury St, Boston, MA, Egyesült Államok

CONTACT INFO

+1234567891
residence@roofiqo.com

SCOPE OF WORK

- ✓ Inspect the existing roof for any damage or issues prior to installation.
- ✓ Remove old roofing materials, including shingles, underlayment, and flashing.
- ✓ Install a new underlayment to provide a moisture barrier prior to shingle installation.
- ✓ Install black asphalt shingles according to manufacturer's specifications, ensuring proper overlap and fastening.
- ✓ Install new flashing around chimneys, vents, and other protrusions as needed.
- ✓ Conduct a thorough inspection of the completed roof to ensure quality and proper installation.

MATERIALS

DESCRIPTION	QUANTITY	UNIT PRICE	TOTAL
Complete Roofing System	17 Squares	$100	**$1,700.00**

LABOR

DESCRIPTION	CREW	RATE	TOTAL
Professional Installation	2 workers × 24 hrs	$45/hr	**$2,160.00**

Materials Subtotal	$1,700.00
Labor Subtotal	$2,160.00
GRAND TOTAL	**$3,860.00**

TERMS & CONDITIONS

1. HIDDEN DAMAGE: Any rotten wood decking or structural damage discovered after removing the existing roof is not included in this estimate Replacement of damaged wood will be billed at an additional cost of $85 per sheet of OSB/Plywood
2. PAYMENT TERMS: 50% deposit is required to schedule the work The remaining 50% is due immediately upon completion
3. RIGHT OF RESCISSION: You the buyer may cancel this transaction at any time prior to midnight of the third business day after the date of this transaction
4. PERMITS: Contractor is responsible for pulling all necessary local permits Permit fees are included in the total cost unless stated otherwise
5. WARRANTY: Contractor provides a 5-year workmanship warranty against leaks Material warranties are provided directly by the manufacturer

PROJECT NOTES

This estimate includes the removal of old roofing materials and the installation of a complete roofing system with black asphalt shingles. All labor is subject to local labor laws and safety regulations.

Customer Acceptance
SIGNATURE & DATE

Roofing LLC
AUTHORIZED REPRESENTATIVE